

D. Finish Schedule Summary

Table 5: Room Finish Schedule Summary

Area of Establishment	Floor				Basecove			Wall					Ceiling		
	Epoxy/Resinous Floor System*	Quarry/Ceramic Tile	NSF # 52 Commercial Vinyl	Other Flooring Products	Coved Ceramic/Quarry	Stainless Steel	Commercial Rubber/Vinyl Base Cove	Stainless Steel	Ceramic Tile	Fiberglass Reinforced Panel	Epoxy painted Concrete Block	Painted Drywall	Metal - Non-Galvanized	Painted Drywall	Vinyl-Coated Acoustic Tiles
Food Prep Area	■	X		■	X	■		X	X	X	X		■	X	X
Cooking Area	■	X		■	X	■		X	X		■		■	X	X
Dish Wash Area	■	X		■	X	■		X	X	X	X		■	X	X
Floorless Walk-in Refrigeration	■	X		■	X	X		NA - Needs to be NSF approved							
Employee Toilet Room	■	X	■	■	X	■	■	X	X	X	X	X	■	X	X
Buffet Area	■	X	X	■	X	■	■	X	X	X	X	■	■	X	X
Service Area	■	X	■	■	X	■	■	X	X	X	X	■	■	X	X
Dry Storage Room	■	X	■	■	X	■	■	X	X	X	X	X	■	X	X

*Materials and finishes not listed must be approved by the Regulatory Authority prior to installation.

Room Finish Schedule Summary Key

	Shaded areas are not allowed.
X	Approved
□	For storage of unopened case lots of single-service food and beverages
■	Pre-approved by the regulatory Authority is required prior to installation.
NA	Not Applicable

*a. A minimum of three initial finish coats of epoxy should be provided and be at least a 1/4" thick for high heat or cold areas or per manufacturer's specifications.

b. A minimum of three initial finish coats of epoxy should be provided and be at least an 1/8" thick for low use areas, limited cooking areas or per manufacturer's specifications.