

Protected Bikeway Feasibility Analysis

Prepared for the City of Minneapolis by Alliant Engineering, Inc.

Final Report — March 4th, 2015







1. Introduction

The City of Minneapolis is preparing an update to the 2011 Minneapolis Bicycle Master Plan. The current plan addresses a broad range of bikeway facility types, including off-street trails, bike boulevards, bike lanes, and shared lanes, but it does not specifically address on-street protected bikeways. The City of Minneapolis also approved a Climate Action Plan in 2013 recommending the implementation of 30 miles of on-street protected bike facilities by 2020. The Bicycle Master Plan update will identify priority locations, capital costs and maintenance costs for the implementation of protected bikeways in Minneapolis. This document has investigated the feasibility of installing protected bikeways on 19 corridors, shown in Figure 1-1. The evaluation will provide supporting information and preliminary concepts for the Bicycle Master Plan update.

Protected Bikeway

A protected bikeway is a bicycle facility that is physically separated from motor vehicle traffic. Off-street trails are the most common type of protected bikeway; however, protected bikeways may also be located within street corridors and separated from traffic lanes through parked cars, curbs, medians, bollards/flexible traffic posts, planters or other vertical feature.

The bicycle network has been expanded significantly in recent years, and a lot of people are biking. However, not everyone feels comfortable and safe riding on a



Photo: Two-Way Protected Bikeway on 36th St W, Minneapolis (2014)

busy street, even with a bike lane. There are some parts of the city where potential bicycling demand is high, but where low-stress bikeway facilities such as trails, bike boulevards, and lower-traffic streets aren't an option. Protected bikeways are designed to feel comfortable and accommodate all bicycle rider types.

Feasibility Analysis

This report provides a summary of the development and methodology to arrive at potential concepts for each corridor. The goal of this report is not to identify a final recommended design, or details of the design; rather, to determine feasibility of implementing a protected bikeway, design considerations, impacts and where feasible, determine a preliminary concept for each corridor. Every corridor is located within a constrained environment. Therefore, changes to rebalance the transportation mode or to generate additional

bike lane width may require street use trade-offs or major reconstruction. As noted, protected bikeways separate the bike lane from the adjacent traffic lane. In general, the feasibility analysis and preliminary concepts identified represent a retrofit of the existing roadway where transportation system trade-offs are required to accommodate an on-street protected bikeway. In a few locations, an off-street facility has been identified. The preliminary concepts for the 19 corridors are illustrated in Figures A-1 through A-19.

Study Process

The feasibility analysis include the following key components:

- Technical Advisory Committee (TAC): The TAC consisted of City of Minneapolis, Hennepin County, and Alliant Engineering staff. Weekly meetings were held throughout the alternatives analysis process to discuss each corridor in detail. The purpose of the meetings was to form a consensus on protected bikeway design parameters, to gain background information, review future plans, discuss feasibility, review conceptual cross-sections, and detail potential impacts for protected bikeways on each of the 19 corridors.
- Documentation of Existing Conditions: The existing conditions for each corridor was documented
 by completing a thorough field review and investigating current aerials, planimetric files, and asbuilt plans that were provided by the City. Criteria that was documented included existing street
 width, travel lane width, sidewalk width, lane assignments, presence of bike facilities, parking
 characteristics, transit services, curb and gutter characteristics, and other elements.
- **Develop Conceptual Cross-Sections and Intersection Improvements:** A range of typical cross-section alternatives for protected bikeway implementation for each corridor was developed. The cross-sections evaluated transportation and street use trade-offs needed to accommodate a protected bikeway. These include:
 - o Lane widths and/or parking widths
 - o Presence of parking
 - o Number of vehicle travel lanes
 - o Sidewalk, median and/or boulevard widths
 - o Curb and gutter characteristics
 - Transit Services
- **High Level Impact Analyses:** For alternatives where eliminating a travel lane was considered, a high level traffic operations analysis was conducted using the existing AM and PM peak hours traffic volumes and signal timing parameters to understand lane removal impacts to traffic operations. The intersection delay was documented, along with an assessment of the impact of removing a travel lane. The analysis was used as a gauge to determine if further analysis was required.
- **Estimate Capital Costs for Each Corridor:** Planning level capital costs for construction were developed for each preliminary concept.




Figure 1-1. Study Corridors

Minneapolis Public Works, 7/11/2014



2. Corridor Evaluation

The objective of the analysis is to provide a high-level evaluation of the feasibility of protected bikeways on 19 corridors in the City of Minneapolis. The study process involved breaking down each corridor into similar segments, developing cross-section alternatives for each segment, detailing the transportation system trade-offs for providing a protected bikeway, and performing an operations analysis on segments where the removal a vehicle travel lane was an option. The following text describes more in depth the evaluation process that was used to form the preliminary concepts.

Corridor Breakdown


Each corridor was segmented based on street widths, parking characteristics; and sections with similar features. For each segment, the street width, daily traffic and bicycle volumes, parking, and State Aid route classification were documented, as well as land use context and connections with the surrounding network. Based on each segment's characteristics, different cross-section options to create dedicated space for a protected bike facility was explored.

Deign Parameters

The protected bikeway design guidelines for one-way, two-way and raised facilities are documented in the NACTO (National Association of City Transportation Officials) Urban Bikeway Design Guidelines as illustrated in Figure 2-1. Based on limited experience from Minneapolis and Hennepin County the ideal geometric parameters for the protected bikeway designs include a 3-foot buffer lane and a 7-foot one-way bike lane (or 10-foot two-way bike lane). In some instances these parameters were not feasible for retrofit conditions and are noted on the preliminary concepts.

Where applicable, Minnesota State Aid standards are considered for vehicle, parking and bicycle lane widths. Every effort is made to meet these design standards. Where this is not possible, or parking or vehicle lane trade-offs cannot be made, a protected bikeway may not be feasible. However, in some cases a design exception could be investigated. Segments requiring a design exception are denoted.

Special consideration was given to segments where there was a 2-foot gutter pan/bituminous seam along with narrow bike lanes. This situation can be uncomfortable or hazardous for bicyclists. In some cases integrant concrete curb may be required. Specifically, the need for integrant curb was identified for two cases. First, is the case of a one-way protected bike facility with a 5-foot bike lane width or less, which also includes the two-foot concrete gutter. In this case, a 5-foot integrant curb is needed to provide a seamless facility for bicyclists. Second is the case of a two-way protected bike facility where the combined two-way bike lane width was 8-feet or less. In this case an integrant curb was assumed at the width of the two-way bike lanes plus the buffer width.



TWO-WAY PROTECTED BIKE LANE IDEAL FOR ONE-WAY STREETS 8.0' TO 12.0' DESIRED WIDTH BUFFER - 3' WHEN NEXT TO PARKING DUE TO DOOR COLLISIONS TRAFFIC BUFFER BIKE LANE LANE LANE 1.5-3.0' 8.0-12.0' BUFFER - MINIMUM OF 1.5' NEXT TO TRAVEL LANE MINIMUM OF 3.0' WHEN NEXT TO PARKING LANE 2-WAY BIKE LANE - MINIMUM OF 8.0' BUT 12.0' IS DESIRED

RAISED PROTECTED BIKE LANE

IDEAL FOR ONE-WAY STREETS
5.0' TO 6.5' DESIRED WIDTH
BUFFER - 3' WHEN NEXT TO PARKING DUE TO DOOR COLLISIONS




Figure 2-1: Protected Bike Lane Best Practice Design (NACTO Guidelines)

Traffic Operations Analysis

For segments with cross-section alternatives where a reduction in the number of vehicle lanes was recommended, a high level traffic operations analysis was performed. Using the industry current SYNCHRO/SIMTRAFFIC software package, approach delays were estimated and evaluated in context of the overall corridor operation and other factors (e.g., bus stop location, bus frequency and pedestrian activity). Based on this analysis, an assessment of the level of congestion was made to determine whether or not the removal of a travel lane is feasible, manageable or if alternative options require further consideration. It is noted that this was a very high level analysis and a more detailed analysis, where applicable, should be completed with preliminary engineering design.

Preliminary Cross-Section Selection

The project team worked closely with City and County staff to develop a selection of potential cross-sections for each segment on each of the 19 corridors. The cross-sections show various strategies to incorporate protected bikeways while detailing the transportation space trade-offs. The cross-section alternatives for each corridor were reviewed and discussed at meetings with the City and County. Ultimately, the cross-sections were narrowed down to one preliminary cross-section for most segments as illustrated in Figure A-1 through Figure A-19. In several cases, there are corridor segments identified as requiring further evaluation or where the implementation of a protected bikeway is not feasible.

Within each segment, there are variations to certain cross-sections that show how they could be modified to accommodate safety and mobility for all transportation modes. These variations include:

- Intersection treatments:
 - o Signal improvements, re-alignment, turn lane or travel lane removal
- Travel lane, parking and bicycle-related treatments:
 - o Lane width reductions, travel lane reduction, turn lane creation, and/or lane for bicycle travel
 - o On-street parking on one side, both sides, and/or removed
 - Designated bike facilities: Bike Boulevards/sharrows/bike lanes (regular, buffered, or protected)

While each cross-section is tailored to a specific segment, it is feasible that certain cross-sections may apply in more than one segment, which should be considered in the forthcoming stages of preliminary design.

3. Intersection Treatments

The feasibility analysis focused largely on the overall corridor bicycle type and typical street cross-sections. However, intersection treatments will need to be considered to make a protected bikeway comfortable and safe for all bicycle rider types. There are a number a strategies that can be employed at intersections to enhance safety and mobility of bicycle travel.

Signal Operation Treatments – The following signal revisions could be considered for protected bike lanes at signalized intersections:

- **Leading Bike/Pedestrian Phasing** Providing a leading bicycle or pedestrian phase gives priority and enables the bicyclist/pedestrian to establish a presence at an intersection.
- **Dedicated Bike Phase** A dedicated bike phase is indicated by bike signal heads and provides a dedicated signal phase for bikes only, separating them from conflicting motor vehicle, LRT, and/or pedestrian movements.
- **Bicycle Detection** Providing bicycle detection at actuated signals to alert the controller of a bike demand. Detection can be provided via a push-button or automated means.

Pavement Marking Treatments – The following pavement marking and signage elements could be considered for protected bike lanes at intersections:

- **Bike Boxes** A bike box is a marked area (typically a green painted zone) ahead of vehicle traffic at a signalized intersection. The bike box allows bicycle traffic to get ahead of queued vehicle traffic when the light turns green and increases visibility.
- **Two-Stage Turn Queue Boxes** A two-stage turn queue box creates a safe route to get bicyclists from one side of the roadway to the opposite side to make a turn. This application basically creates a two-step safe crossing route to get to the desired side of the roadway through pavement markings and signage.
- Intersection Conflict Zone Markings Pavement markings that provide a clear path for bicyclists and vehicle drivers through an intersection. The pavement markings raise awareness for both motorists and bicyclists to potential conflict areas.
- Mixing Zones A mixing zone is an area where vehicle traffic merges into a bike lane by yielding to bike traffic to prepare for a turn. Mixing zones are generally characterized by dashed bike lane lines and/or specialize pavement markings to denote a shared area. For this study, the mixing zones are assumed at all unsignalized and signalized intersections.

Concrete Related Construction Treatments – The following construction elements could be considered for protected bike lanes:

- Integrant Curb Integrant curb of varying widths has been assumed on many corridors. Integrant curb was assumed to eliminate the standard 2-foot gutter pan and, in turn, provide a seamless travel lane for bicyclists.
- **Curb Extensions** A curb extension is constructed by increasing the sidewalk/curb area and narrowing the roadway. Curb extensions increase pedestrian safety by decreasing the crossing distance and making pedestrians more visible.
- Medians/Refuge Islands A median or refuge island can be installed in the center of an approach leg at intersections to facilitate crossings of higher volume two-way streets. The median or refuge island allows bicycle or pedestrians to cross one direction at a time and provides a safe haven between traffic directions. The median or refuge island also acts a traffic calming measure for approaching vehicles as they slow down to navigate the in street obstacle.
- Raised Barrier The provision of a raised barrier, as opposed to flexible delineator posts, may be advantageous at locations where additional separation is needed.

Detailed evaluation and identification of intersection treatments will be necessary during preliminary engineering of the corridors. The feasibility analysis identified key intersections that will require attention and in some cases evaluated possible bicycle treatments. For this study many intersection treatments were assumed and are detailed in the Preliminary Concept Figures and in the Cost Estimates. This section

highlights strategies that were assumed and additional treatments that should be considered during preliminary engineering design.

4. Capital Costs

A planning level capital cost estimate for each corridor was prepared based on the basic cross-section and corridor information detailed on each preliminary concept layout. Corridor specific construction elements such as integrant curb, medians, curb extensions, diverters, etc. were included were included in the estimates where noted. Additionally, annual maintenance costs provided by the city, were included for each corridor section. The following details the general cost assumptions for each category:

Pavement Marking & Signage

- Removal of all existing pavement markings.
- 12 inch painted markings (latex paint) were assumed for all buffered lanes or protected bikeway buffer hatching and all stop bar locations. Hatching spacing was assumed to be 25 feet.
- For the buffer zones, 6 inch solid white paint is assumed for the longitudinal striping next to vehicle traffic and 4" solid white paint is assumed for striping next to the bike lane.
- Bike message symbols in the bike lanes are assumed to be thermoplastic and spaced one per direction per block.
- All longitudinal pavement markings are assumed to be paint and all symbols are assumed to be thermoplastic material.
- Conflict zone markings (colored and dashed) are assumed in the intersection crossing of each unsignalized and signalized intersections.
- All crosswalks and stop bars are assumed to be remarked with latex paint.
- For a one-way and two-way protected bike lanes 5 sign assemblies per block, on average, are assumed (includes removal and new panels or panel relocations).
- Mobilization was assumed to be 5% of the total cost. Traffic Control was assumed to be 8% of the total cost.

Delineation

• Flexible delineator posts are assumed at an average 25 foot spacing. The total number of delineators was increased by 10 percent.

Signal Modifications

• Signal modifications are assumed at every signalized intersection to account for signal operation changes (phasing or added signal indications or countdown timers or bike phasing). In general,

simple revisions were assumed at two-phased signals and more complex revisions were assumed at signals with left turn phasing.

Construction Elements

- For one-way protected bike lanes where there is a 2-foot gutter seam and the bike lane width is 5-feet or less, the section will be replaced with integrant curb.
- For two-way protected bike lanes where there is a 2-foot gutter seam and the two-way bike lane width is 8-feet or less, the section will be replaced with integrant to the outer edge of the buffer.
- Corridor specific construction elements such as off-street trails, medians and curb extensions were added to some corridors as denoted on the preliminary concept figures.

Other Costs

- Seal coating was assumed on all bituminous roadways where pavement markings are being removed.
 Concrete roadways would not be seal coated.
- 25% contingency was assumed for all corridors.

The capital construction costs are summarized in Table 1.

Table 1. Capital Cost and Corridor Summary

| Section | | Capital Costs | | | | |
|--|---|-----------------|-----------------|--------------------------|---|--|
| | Signs, Pavement Markings & Delineators | Signals | Seal Coat | Construction Elements | Total Cost (Includes 25% Contingency) | |
| 1A - 24th St from Hennepin Ave to Hiawatha Ave | NA ¹ | NA^1 | NA ¹ | NA ¹ | NA^1 | |
| 1B - Franklin Ave from Hennepin Ave to Bloomington Ave S | NA ¹ | NA ¹ | NA ¹ | NA ¹ | NA ¹ | |
| 2A - Franklin Ave from Bloomington Ave S to 20th Ave S | \$75,000 | \$35,000 | \$0 | \$20,000 | \$163,000 | |
| 2B - Franklin Ave from 28th Ave S to Seabury Ave | \$65,000 | \$20,000 | \$40,000 | \$20,000 | \$182,000 | |
| 2C - Franklin Ave from 20th Ave S to 28th Ave S | NA ¹ | NA ¹ | NA ¹ | NA ¹ | NA ¹ | |
| 3A - Franklin Ave SE from Thornton St SE to Emerald SE | NA ¹ | NA ¹ | NA ¹ | NA ¹ | NA ¹ | |
| 4A - Lyndale Ave S from Franklin Ave to Loring Greenway Bridge | \$105,000 | \$100,000 | \$0 | \$640,000 | \$1,057,000 | |
| 4B - Lyndale Ave S from Oak Grove St to Dunwoody Blvd | \$10,000 | \$100,000 | \$0 | \$35,000 | \$57,000 | |
| 4C - Hennepin Ave from Oak Grove St to Maple St | \$20,000 | \$5,000 | \$0 | \$33,000 | \$37,000 | |
| 5A - Dunwoody Blvd Trail | \$30,000 | \$5,000 | \$0 | \$215,000 | \$313,000 | |
| 5B - Hennepin Ave from Maple St to 12th St N | \$15,000 | \$3,000 | \$0 | \$215,000 | \$19,000 | |
| 5C - 1st Ave from 12th St N to 1st Ave N | \$13,000 | \$20,000 | \$75,000 | \$0 | \$269,000 | |
| 5D - Hennepin Ave from Washington Ave to 1st Ave N | \$40,000 | \$10,000 | \$30,000 | \$0 | \$100,000 | |
| 5E - Hennepin Ave from 12th St N to Washington Ave | NA ¹ | NA ¹ | NA ¹ | NA ¹ | NA ¹ | |
| | \$150,000 | \$60,000 | \$50,000 | | \$638,000 | |
| 6A-Hennepin Ave/1st Ave NE from 1st St N to 5th St NE | \$150,000 NA ¹ | <u> </u> | | \$250,000 | NA ¹ | |
| 6B - 5th St NE from Hennepin Ave to 3rd Ave NE | | NA ¹ | NA ¹ | NA ¹ | | |
| 7A - Grant St W from Willow St to Marquette Ave | \$40,000 | \$10,000 | \$30,000 | \$30,000 | \$138,000 | |
| 7B - Marquette Ave/2nd Ave S from 1st Ave S to Washington Ave | \$230,000 | \$235,000 | \$45,000 | \$25,000 | \$669,000 | |
| 8A - Park/Portland Ave from 46th St E to Franklin Ave E | \$580,000 | \$115,000 | \$780,000 | \$0 | \$1,844,000 | |
| 8B - Park/Portland Ave from Franklin Ave E to West River Pkwy | \$290,000 | \$125,000 | \$310,000 | \$0 | \$907,000 | |
| 8C - Park/Portland Ave from Minneahaha Pkway to 46th St E | NA ¹ | NA ¹ | NA ¹ | NA ¹ | NA ¹ | |
| 9A-1st Ave S/Blaisdell Ave from 40th St E to Grant St W | \$410,000 | \$260,000 | \$420,000 | \$30,000 | \$1,400,000 | |
| 10A - 6th St S from Hennepin Ave to Park Ave & Trail from Park to Chicago | \$95,000 | \$55,000 | \$90,000 | \$130,000 | \$463,000 | |
| 10B - 11th Ave S from 6th St S to 2nd St S | \$75,000 | \$20,000 | \$35,000 | \$0 | \$163,000 | |
| 10C - 5th St S from 1st Ave N to Chicago Ave S | NA ¹ | NA ¹ | NA ¹ | NA ¹ | NA ¹ | |
| 11A - 7th St N from Plymouth Ave N to 1st Ave N | \$180,000 | \$70,000 | \$140,000 | \$0 | \$488,000 | |
| 11B - 10th St S from 7th/10th Split to Park Ave | \$155,000 | \$85,000 | \$95,000 | \$0 | \$419,000 | |
| 11C - 9 St S from 1st Ave to Park Ave | \$115,000 | \$60,000 | \$105,000 | \$0 | \$350,000 | |
| 12A - University Ave SE from 1st Ave NE to Oak St SE | \$225,000 | \$80,000 | \$190,000 | \$240,000 | \$919,000 | |
| 12B - Oak St SE from E River Pkwy to Washington Ave SE | \$35,000 | \$10,000 | \$40,000 | \$0 | \$107,000 | |
| 12C - Oak St SE from Washington Ave SE to Walnut St | \$60,000 | \$25,000 | \$35,000 | \$180,000 | \$375,000 | |
| 12D - 4th St SE from 1st Ave NE to Walnut St | NA ¹ | NA ¹ | NA ¹ | NA ¹ | NA ¹ | |
| 13A - 15th Ave SE from University Ave to Rollins Ave SE | \$105,000 | \$65,000 | \$45,000 | \$125,000 | \$425,000 | |
| 13B - Rollins Ave SE/18th Ave SE from 15th Ave SE to Como Ave SE | \$25,000 | \$0 | \$10,000 | \$85,000 | \$150,000 | |
| 13C - 18th Ave SE from Como Ave SE to E Hennepin Ave | \$35,000 | \$10,000 | \$25,000 | \$0 | \$88,000 | |
| 13D - 15th Ave SE/Como Ave SE from Rollins Ave SE to 18th Ave SE | NA ¹ | NA ¹ | NA ¹ | NA ¹ | NA ¹ | |
| 14A - 20th Ave S from Minnehaha Ave to Riverside Ave | \$70,000 | \$10,000 | \$40,000 | \$20,000 | \$175,000 | |
| 14B - 19th Ave S/10th Ave S from Riverside Ave to 5th St SE | \$125,000 | \$60,000 | \$65,000 | \$0 | \$313,000 | |
| 15A-Emerson Ave N from Plymouth Ave N to 33rd Ave N (Cost Out as a TWPBL) | \$140,000 | \$40,000 | \$135,000 | \$0 | \$394,000 | |
| 15B-Emerson/Fremont Ave N from Plymouth Ave N to 33rd Ave N (Cost Out as a OWPBL PAIR) | \$215,000 | \$75,000 | \$255,000 | \$0 | \$682,000 | |
| 16A-Plymouth Ave N/8th Ave NE from Fremont Ave N to 5th St NE | \$255,000 | \$65,000 | \$135,000 | \$0 | \$569,000 | |
| 17A-Main St/Marshall St NE from Hennepin Ave to 14th Ave NE | \$130,000 | \$40,000 | \$135,000 | \$0 | \$382,000 | |
| 17B-Marshall St NE from 14th Ave NE to Lowry Ave NE | \$70,000 | \$10,000 | \$90,000 | \$0 | \$213,000 | |
| 18A-3rd Ave from Washington Ave S to 5th St NE | \$160,000 | \$65,000 | \$75,000 | \$0 | \$375,000 | |
| 18B - 3rd Ave from E Franklin Ave to Washington Ave S | NA ¹ | NA^1 | NA ¹ | NA ¹ | NA ¹ | |
| 19A-Washigton Ave | \$195,000 | \$60,000 | \$165,000 | \$0 | \$525,000 | |

¹ Costs were not calculated for these segments as no construction work is proposed. If the segment is an existing facility, it will remain as such or a future bike facility type is not yet determined.

⁻Pavement Marking Unit Costs Assume: Removal at \$10.00 per SF and \$0.55 per LF. Thermoplastic Symbols (New Biker Message a \$350.00 each, Bike Boulevard Symbol at \$900.00 each), 12" Stop Bar/Buffer Paint Lines at \$1.50 per LF, 4" Longitudinal Paint Lines at \$0.25 per LF, 6" Longitudinal Paint Lines at \$0.50 per LF, Unisignalized Mixing Zone at \$400 Each Approach, Signalized Mixing Zone at \$3,000 Each Approach.

⁻Signal Revisions: Assume a Revision at All Signals (Simple Signals Without Left Turn Phasing \$5,000 Each, Complex Signals With Left Turn Phasing \$10,000 Each).

⁻Seal Coat Assume: \$4.00 per SQ YD.

⁻Delineators Assume: \$100.00 Each. Number of Delineators Was Increased by 10%.

⁻Signs Assume: \$200.00 Each Sign Post Assembly.

⁻Off-Street Trail: \$65 per LF (Does not assume ROW Cost or Acquisition)




Appendix A:

Preliminary Corridor Concepts

FRANKLIN OR 24TH STREET (HENNEPIN TO HIAWATHA)-CONCEPT DESIGN 1

PROTECTED BIKE LANES ARE NOT FEASIBLE ON FRANKLIN AVE. OTHER ALTERNATIVE BIKE FACILITY TREATMENTS SHOULD BE EXPLORED.



24TH ST FROM I-35W TO CEDAR - MAINTAIN EXISTING BIKE LANES. PROTECTED BIKE LANES ARE NOT FEASIBLE WITHIN EXISTING ROADWAY WIDTH.

PORTLAND AVE TO PARK AVE: **BIKE LANE IN BOTH DIRECTIONS** ARE FEASIBLE WITH PERMANENT PARKING REMOVAL. (BOTH SIDES)

24TH ST FROM HENNEPIN AVE TO I-35W - CONSIDER STANDARD BIKE LANES AND/OR SHARED LANE FACILITIES. FURTHER EVALUATION MAYBE NECESSARY:

1. MAINTAIN EXISTING PARKING.

PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY

- 2. EXCLUSIVE BIKE LANE IN ONE DIRECTION WITH A SHARED LANE IN THE OTHER DIRECTION; OR
- 3. SHARED LANE FACILITY IN BOTH DIRECTIONS: OR

PLANNED RECONSTRUCTION OF

PEDESTRIAN/BIKE BRIDGE

- 4. BIKE LANE IN BOTH DIRECTIONS ON BLOCKS WHERE THERE CURRENTLY IS NO PARKING.
- 5. TRAFFIC SIGNAL IMPROVEMENTS ARE NOT EXPECTED NECESSARY. (PRETIMED OPERATION)

(c)


NICOLLET AVE TO 3RD AVE S: 39-40' WITH PARKING. SHARED LANES OR ADVISORY LANES FEASIBLE. BIKE LANES FEASIBLE WITH PARKING REMOVAL

3RD AVE TO 4TH AVE: 32' WITH PARKING ON NORTH SIDE. SHARED LANES ARE FEASIBLE. BIKE LANES ARE FEASIBLE WITH PARKING REMOVAL

HENNEPIN AVE TO LYNDALE AVE: 36'
PARKING ON SOUTH SIDE, SHARED LANE
FEASIBLE. BIKE LANE FEASIBLE WITH PARKING REMOVAL

LYNDALE AVE TO GARFIELD AVE: 38' NO PARKING. BIKE LANE FEASIBLE.

BLAISDELL AVE TO NICOLLET AVE: 34' SUNDAY PARKING ON SOUTH SIDE. SHARED LANE FEASIBLE. BIKE LANE FEASIBLE WITH PARKING REMOVAL.



(D) GARFIELD AVE TO BLAISDELL AVE

LEGEND OFF-STREET TRAIL

FUTURE OFF-STREET TRAIL PROTECTED BIKE LANE

EXISTING BIKE LANE

SPECIAL INTERSECTION TREATMENT MAY BE NEEDED

DELINEATOR

PARKING REMOVAL TRAVEL LANE REMOVAL

ADD PARKING

OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.





233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 MAIN 612.758.3099 FAX www.alliant-inc.com

STANDARD BIKE LANE

BUFFERED BIKE LANE

BIKE BOULEVARD

SHARED BIKE LANE

BIKEWAY TYPE OPTIONS

FURTHER EVALUATION OF

REVIEW ALTERNATIVE ROUTE OR

LONGER-TERM OPTIONS REQUIRED


PROTECTED BIKEWAYS FEASIBILITY ANALYSIS

FRANKLIN OR 24TH STREET (HENNEPIN TO HIAWATHA) PRELIMINARY CONCEPT CORRIDOR 1

FIGURE A-1

NOTE:

FRANKLIN AVE (HIAWATHA TO RIVER) - CONCEPT DESIGN 2



PUBLIC WORKS

612.758.3099 FAX

www.alliant-inc.com

ALLIANT


(HIAWATHA TO RIVER)

PRELIMINARY CONCEPT CORRIDOR 2

1 OF 2


3/4/2015 X:\2014\140091\DESIGN\P|anShee NOTE:

FRANKLIN AVE (HIAWATHA TO RIVER) - CONCEPT DESIGN 2




*8' CONCRETE INTEGRANT CURB AND GUTTER (POOR CONDITION)

(1A) BLOOMINGTON AVE TO CEDAR AVE



(2A) CEDAR AVE TO MINNEHAHA AVE



(B) 20TH AVE S TO 28TH AVE S

*SOME BLOCKS WITH 2' GUTTER PAN / BITUMINOUS SEAM AND OTHERS WITH BITUMINOUS OVERLAY

(C) 28TH AVE S TO SEABURY AVE -BIKE/BUFFER WIDTH LESS THAN 10'

PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.






233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 MAIN www.alliant-inc.com

PROTECTED BIKEWAYS FEASIBILITY ANALYSIS FRANKLIN AVE (HIAWATHA TO RIVER) PRELIMINARY CONCEPT CORRIDOR 2

FIGURE A-2 2 OF 2

NOTE:

FRANKLIN AVE SE - CONCEPT DESIGN 3



PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.









233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 MAIN www.alliant-inc.com

FURTHER EVALUATION OF

LONGER-TERM OPTIONS REQUIRED


PROTECTED BIKEWAYS FEASIBILITY ANALYSIS FRANKLIN AVE SE

PRELIMINARY CONCEPT CORRIDOR 3

FIGURE A-3

TRAVEL LANE REMOVAL

ADD PARKING




CORRIDOR 4

3:19:24 PM 3/4/2015

HENNEPIN OR 1ST & DUNWOODY-CONCEPT DESIGN 5 DUNWOODY BLVD FROM CEDAR LAKE TRAIL TO DUNWOODY INSTITUTE - OFF-STREET TRAIL IS RECOMMENDED. THE OFF-STREET TRAIL WILL CROSS FROM THE NORTH SIDE OF DUNWOODY BLVD TO THE SOUTH SIDE AT THE SIGNAL. CONSIDER INTERSECTION MODIFICATIONS. ON-STREET PROTECTED BIKE FACILITY IS NOT FEASIBLE. CONSIDERATIONS: 1. PROVIDE OFF STREET TRAIL ON SOUTH SIDE OF DUNWOODY. MAKE CONNECTIONS TO LORING PARK AND DOWNTOWN AT LYNDALE AVE INTERSECTION (SEE ALSO CORRIDOR 4) RECONSTRUCT PORK CHOP ISLANDS TO **FACILITATE SAFE BIKE MOVEMENTS** DUNWOODY BLVD- A TWO WAY PROTECTED BIKEWAY IS FEASIBLE ON SOUTH SIDE. CONSIDERATIONS: 1. PROVIDE CONNECTIONS TO HENNEPIN AVE INTO DOWNTOWN AND LORING PARK (SEE CORRIDOR 4) 2. PROVIDE CONNECTION TO FUTURE DUNWOODY BLVD OFF STREET TRAIL 1ST AVE FROM 12TH ST TO 1ST ST - ONE-WAY PROTECTED BIKE LANES THROUGH ADDING DELINEATORS TO EXISTING BUFFERS 1. ADD BUFFER/DELINEATORS TO ALL BLOCKS. RELOCATE OR REMOVE **IMPROVE CONNECTION EB BUS STOP** 2. CONSIDER PURSUING A DESIGN EXCEPTION BETWEEN 7TH ST AND 12TH ST TO PROVIDE PROTECTED BIKE LANES WITH A BUFFER. TO 12TH ST 3. FURTHER EVALUATION OF LONG TERM FACILITY IN CONJUCTION WITH HENNEPIN AVE IS NEEDED. **LEGEND** STANDARD BIKE LANE **OFF-STREET TRAIL FUTURE OFF-STREET TRAIL** BUFFERED BIKE LANE PROTECTED BIKE LANE EXISTING BIKE LANE **BIKE BOULEVARD** SPECIAL INTERSECTION TREATMENT MAY BE NEEDED SHARED BIKE LANE **DELINEATOR** REVIEW ALTERNATIVE ROUTE OR **BIKEWAY TYPE OPTIONS** PARKING REMOVAL HENNER TO AVE FURTHER EVALUATION OF TRAVEL LANE REMOVAL LONGER-TERM OPTIONS REQUIRED HENNEPIN AVE HENNEPIN AVE HENNEPIN AVE ADD PARKING HENNEPIN AVE FROM LYNDALE AVE TO 12TH ST - MAINTAIN **EXISTING BUFFERED BIKE LANES** 1. EVALUATE CONNECTIONS TO WASHINGTON AVE CYCLE TRACK. 2. COORDINATE WITH STREET CAR PLAN AND CONSIDERSTIONS 1. ADD DELINEATORS TO THE EXISTING BUFFER. 2. MAINTAIN BUFFER ONLY IN AREAS ADJACENT TO PARKING HENNEPIN AVE FROM 12TH ST S TO 1ST ST N - PROTECTED BIKE LANES ARE NOT FEASIBLE WITH IN EXISTING CURBS. MAINTAIN TWO WAY PROTECTED BIKEWAY (SEE CORRIDOR 4) MAINTAIN CONNECTION FROM OFF-STREET TRAIL TO ON-STREET BIKE LANE. NOTE:

PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING. EXISTING SHARED LANE BIKE FACILITY. FURTHER EVALUATION OF LONG TERM BICYCLE FACILITY IS NECESSARY. MAINTAIN PROTECTED BIKE LANES ON 1ST AVE N PENDING FUTURE CHANGES ON HENNEPIN AVE.











233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 MAIN **ALLIANT** 612.758.3099 FAX www.alliant-inc.com


PROTECTED BIKEWAYS FEASIBILITY ANALYSIS HENNEPIN OR 1ST & DUNWOODY PRELIMINARY CONCEPT CORRIDOR 5


FIGURE A-5 1 OF 2




3:19:29 PM 3/4/2015








(B)BRIDGE (3 TRAVEL LANE OPTION IS SHOWN) -BIKE/BUFFER WIDTH LESS THAN 10'



1ST AVE NE FROM UNIVERSITY AVE 4TH ST NE



 (κ) 1ST AVE NE FROM 4TH ST NE TO 5TH ST NE





233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 MAIN 612.758.3099 FAX www.alliant-inc.com


PROTECTED BIKEWAYS FEASIBILITY ANALYSIS HENNEPIN/1ST NE & 5TH ST NE PRELIMINARY CONCEPT CORRIDOR 6

FIGURE A-6 2 OF 2


MARQUETTE &/OR 2ND AVE S AND GRANT - CONCEPT DESIGN 7 GRANT ST FROM WILLOW TO LASALLE - TWO-WAY PROTECTED BIKE FACILITY ON THE SOUTH SIDE OF THE STREET THROUGH NARROWING LANES. GRANT ST FROM LASALLE TO MARQUETTE - TWO-WAY PROTECTED BIKE FACILITY ON THE SOUTH SIDE OF THE STREET THROUGH THE REMOVAL OF AN EASTBOUND TRAVEL LANE MARQUETTE AVE FROM GRANT ST TO 12TH ST **DESIGN CONSIDERATIONS:** 1. SOUTHBOUND BIKES ARE PERMITTED IN BUS LANE AND WILL TRAIL HEAD CONNECTION AT LORING SERVE AS A CONNECTION DURING OFF PEAK PERIODS. 2. A STANDARD BIKE LANE COULD BE USED IN THE NORTHBOUND (SOUTH SIDE OF GRANT ST - BIKE PATH DIRECTION WITHOUT REQUIRING A DESIGN EXCEPTION. TRAILHEAD NEAR YALE PL & WILLOW ST) SIGHT LINE OBSTRUCTION AT PARKING RAMP DRIVEWAY(BLIND APPROACH) FURTHER INVESTIGATION INTO PARKING MARQUETTE FROM GRANT TO WASHINGTON - ONE-WAY PROTECTED REMOVAL MAY BE NEEDED IF NARROW BIKE FACILITY ON THE NORTH SIDE OF THE STREET THROUGH LANE TRAVEL WAY BECOMES PROBLEMATIC. NARROWING. FURTHER EVALUATION OR CONSIDERATIONS INCLUDE: 1. TRANSIT IMPACTS (11' LANE OPERATION) 2. FOOD TRUCK VENDOR OPERATIONS AND CONFLICT WITH BIKE LANE. 3. DESIGN EXCEPTION REQUIRED ON MARQUETTE (GRANT TO WASHINGTON) AND 2ND AVE (12TH TO WASHINGTON) 4. PROVIDE BIKE TURN BOXES AT E/W BIKE LANE STREETS MARQUETTE AVE MARQUETTE AVE 2ND AVE S **REMOVE EB** TRAVEL LANE ST Ē /ASHINGT **INTERSECTION IMPROVEMENTS:** 1. EXCLUSIVE BIKE SIGNAL PHASE IS FEASIBLE 2. COLORED BIKE LANE MARKINGS RELOCATE FOOD TRUCKS REMOVE WB TRAVEL LANE LEGEND FURTHER EVALUATION IS NEEDED: 1. SIGNAL OPERATION TREATMENT TO CONNECT NORTHBOUND OFF-STREET TRAIL STANDARD BIKE LANE BIKES TO 2ND AVE BUS LANE DURING OFF PEAK PERIODS. (SEGMENT D TO F - TRANSITION BIKES FROM LEFT SIDE TO **BUFFERED BIKE LANE FUTURE OFF-STREET TRAIL** RIGHT SIDE OF ROAD) PROTECTED BIKE LANE **EXISTING BIKE LANE** 2. CONFLICT ZONE LANÉ MARKINGS. SPECIAL INTERSECTION TREATMENT **BIKE BOULEVARD** MAY BE NEEDED 2ND AVE FROM GRANT TO WASHINGTON SHARED BIKE LANE ONE-WAY PROTECTED BIKE FACILITY **DELINEATOR** NOTE: REVIEW ALTERNATIVE ROUTE OR THROUGH LANE NARROWING. **BIKEWAY TYPE OPTIONS** PARKING REMOVAL PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY **FURTHER EVALUATION OF** TRAVEL LANE REMOVAL OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. LONGER-TERM OPTIONS REQUIRED CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING. ADD PARKING PROTECTED BIKEWAYS FEASIBILITY ANALYSIS **FIGURE** 233 Park Ave S, Ste 300 MINNEAPOLIS MARQUETTE &/OR 2ND AVE S Minneapolis, MN 55415 A-7 DEPARTMENT OF 612.758.3080 MAIN ALLIANT 612.758.3099 FAX AND GRANT PUBLIC WORKS www.alliant-inc.com 1 OF 2

PRELIMINARY CONCEPT CORRIDOR 7

MARQUETTE &/OR 2ND AVE S AND GRANT - CONCEPT DESIGN 7




-BIKE/BUFFER WIDTH LESS THAN 10'




12TH ST S TO WASHINGTON AVE -DESIGN EXCEPTION REQUIRED -BIKE/BUFFER WIDTH LESS THAN 10'

NOTE:


PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.



(B) LASALLE AVE TO 1ST AVE S



(D) 1ST AVE S TO 12TH ST S



12TH ST S TO WASHINGTON AVE -DESIGN EXCEPTION REQUIRED -BIKE/BUFFER WIDTH LESS THAN 10'






233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 MAIN ALLIANT 612.758.3099 FAX www.alliant-inc.com


PROTECTED BIKEWAYS FEASIBILITY ANALYSIS MARQUETTE &/OR 2ND AVE S AND GRANT PRELIMINARY CONCEPT CORRIDOR 7

FIGURE A-7 2 OF 2




3:19:57 PM 3/4/2015

PARK AVE & PORTLAND AVE-CONCEPT DESIGN 8




*8' CONCRETE INTEGRANT CURB AND GUTTER AND OTHERS WITH 2' GUTTER PAN / BITUMINOUS SEAMS


PORTLAND AVE - 46TH ST TO 31ST ST & 29TH ST TO FRANKILIN AVE



PORTLAND AVE - WASHINGTON AVE TO 2ND ST




PARK AVE - 46TH ST TO 31ST ST & 28TH ST TO I-94 BRIDGE




*8' CONCRETE INTEGRANT CURB AND GUTTER, OTHERS
WITH 2' GUTTER PAN / BITUMINOUS SEAMS AND BRIDGE DECK


PORTLAND AVE - 31ST ST TO 29TH ST & FRANKILIN AVE TO 6TH ST




PORTLAND AVE - 2ND ST TO W RIVER PKWY



G PARK AVE - 31ST ST TO 28TH ST & I-94 BRIDGE TO 5TH ST S



PARK AVE - MINNEHAHA PKWY TO 46TH ST



PARK AVE - WASHINGTON AVE TO 2ND ST



PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.







233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 MAIN ALLIANT 612.758.3099 FAX www.alliant-inc.com

PROTECTED BIKEWAYS FEASIBILITY ANALYSIS PARK/PORTLAND PRELIMINARY CONCEPT CORRIDOR 8

FIGURE A-8 2 OF 2



3:20:09 PM 3/4/2015



MINNEAPOLIS
DEPARTMENT OF
PUBLIC WORKS




233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 Maln 612.758.3099 FAX www.alliant-inc.com PROTECTED BIKEWAYS FEASIBILITY ANALYSIS

1ST/BLAISDELL

PRELIMINARY CONCEPT

CORRIDOR 9

FIGURE A-9 2 OF 2




www.alliant-inc.com


1 OF 2

CORRIDOR 10

5TH &/OR 6TH ST S & 11TH AVE - CONCEPT DESIGN 10




- (A1) 6TH ST HENNEPIN AVE TO 4TH AVE S
- 6TH ST 4TH AVE S TO PARK AVE -BIKE/BUFFER WIDTH LESS THAN 10'




*2' GUTTER PAN / BITUMINOUS AND OTHERS WITH 8' CONCRETE INTEGRANT CURB AND GUTTER (POOR CONDITION)


(A2) 6TH ST - HENNEPIN AVE TO 4TH AVE S




(B2) 6TH ST - 4TH AVE S TO PARK AVE




(D) 5TH ST - 5TH AVE S TO PARK AVE S





**2' GUTTER PAN / BITUMINOUS SEAM

11TH AVE - 6TH ST S TO 3RD ST S * PROTECTED BIKE LANES WILL NOT FIT IN THE **EXISTING 3-LANE CROSS-SECTION. REDUCTION** TO ONE SOUTHBOUND LANE CAN OCCUR WHEN THE NEW 7TH ST/94 RAMP CONNECTION IS COMPLETED.





**2' GUTTER PAN / BITUMINOUS SEAM


(G) 11TH AVE - 3RD ST S TO W. RIVER PARKWAY *PARKING REMOVAL ON ONE SIDE IS REQUIRED BETWEEN 2ND ST AND W. RIVER PARKWAY (53' STREET WIDTH).

NOTE:

PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.









CORRIDOR 11

3:20:49 PM 3/4/2015


7TH ST N & 9TH/10TH ST S - CONCEPT DESIGN 11




- *6' CONCRETE INTEGRANT CURB AND GUTTER WITH 2' GUTTER PAN / BITUMINOUS SEAMS
- (A) 7TH ST N 12TH AVE N TO OLSON MEMORIAL HWY/6TH AVE N BIKE/BUFFER WIDTHS LESS THAN 10'




- (D) 10TH ST HAWTHORNE AVE N TO 4TH AVE S -BIKE/BUFFER WIDTHS LESS THAN 10'




- *2' GUTTER PAN / BITUMINOUS SEAMS
- (H)9TH ST 1ST AVE N TO HENNEPIN AVE BIKE/BUFFER WIDTHS LESS THAN 10'



(B) 7TH ST N - OLSON MEMORIAL HWY TO 9TH/10TH ST N SPLIT -BIKE/BUFFER WIDTHS LESS THAN 10'




- *2' GUTTER PAN / BITUMINOUS SEAMS
- 10TH ST 4TH AVE S TO PARK AVE -BIKE/BUFFER WIDTHS LESS THAN 10'




7TH/10TH ST N SPLIT TO 2ND AVE N -BIKE/BUFFER WIDTHS LESS THAN 10'

OR




- *2' GUTTER PAN / BITUMINOUS SEAMS AND OTHERS
- 10TH ST GLENWOOD TO HAWTHORNE -DESIGN EXCEPTION REQUIRED BIKE/BUFFER WIDTHS LESS THAN 10'






- (G) 7TH ST N 2ND AVE N TO 1ST AVE N -BIKE/BUFFER WIDTHS LESS THAN 10'



- 9TH ST HENNEPIN AVE TO PARK AVE -BIKE/BUFFER WIDTHS LESS THAN 10'



(12) 9TH ST - HENNEPIN AVE TO PARK AVE -BIKE/BUFFER WIDTHS LESS THAN 10'

NOTE:

PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.






233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 MAIN www.alliant-inc.com


PROTECTED BIKEWAYS FEASIBILITY ANALYSIS 7TH ST N & 9TH/10TH ST S PRELIMINARY CONCEPT CORRIDOR 11

FIGURE A-11 2 OF 2




CORRIDOR 12

4TH ST SE/UNIVERSITY AVE SE & OAK ST - CONCEPT DESIGN 12



A UNIVERSITY AVE - 1ST AVE NE TO CENTRAL AVE NOTE: A ONE-WAY PROTECTED BIKE LANE IS FEASIBLE. A LANE REMOVAL IS STILL NECESSARY




*WIDTH VARIES ALONG UNIVERSITY AVE


** COULD ADD ON-STREET PARKING 10 TH 52' WIDE BLOCKS-13TH AVE TO 15TH AVE

***2' GUTTER PAN / BITUMINOUS SEAMS


(D1) UNIVERSITY AVE - 10TH AVE TO OAK ST



(I) 4TH STREET - 15TH AVE TO 13TH AVE



B UNIVERSITY AVE - CENTRAL AVE TO 8TH AVE NOTE: A ONE-WAY PROTECTED BIKE LAWE IS FEASIBLE.




*WIDTH VARIES ALONG UNIVERSITY AVE


** 6' GUTTER PAN FOR BIKE LANE.

(MAY REQUIRE REPLACE CONCRETE PANELS WIDTH 8')


D2 UNIVERSITY AVE - 10TH AVE TO OAK ST
-DESIGN EXCEPTION REQUIRED ON 42 FOOT WIDE BLOCKS
42' SECTION IS LOCATED BETWEEN 15TH AVE TO 16TH AVE
AND 17TH AVE TO 18TH AVE




(C) UNIVERSITY AVE - 8TH AVE TO 10TH AVE



(E) 4TH STREET - CENTRAL AVE TO HENNEPIN AVE



(E) 4TH STREET - HENNEPIN AVE TO 1ST AVE



(J) OAK STREET - WASHINGTON AVE SE TO WALNUT ST (K) OAK STREET - EAST RIVER PARKWAY TO WASHINGTON AVE SE

NOTE:

1. PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.





233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 MalN 612.758.3099 FAX www.alliant-inc.com PROTECTED BIKEWAYS FEASIBILITY ANALYSIS
4TH/UNIVERSITY & OAK ST
PRELIMINARY CONCEPT
CORRIDOR 12

FIGURE A-12 2 OF 2

15TH ST SE TO NE DIAGONAL - CONCEPT DESIGN 13 15TH AVE SE - ONE-WAY PROTECTED BIKE LANES ARE FEASIBLE. CONSIDERATIONS RECONSTRUCT SE 1. REMOVE CENTER TURN LANE BETWEEN **CORNER TO PROVIDE** 5TH ST AND 4TH ST. IMPROVED BIKE 2. MAINTAIN SB LEFT TURN LANE AT 5TH ST. **CONNECTION TO CROSSWALK AND** TWO-WAY PROTECTED BIKE LANE ON THE DIAGONAL TRAVEL NORTH SIDE. 1. RELOCATE ON STREET PARKING TO THE SOUTH SIDE. FURTHER EVALUATION OF BIKE MAINTAIN EXISTING LANE CONNECTION REQUIRED BY PRELIMINARY ENGINEERING. BIKE LANE FACILITY. **CONSIDERATIONS:** I. TURN BOXES 2. PROVIDE BIKE SIGNAL (A)Ω 15TH AVE 15TH AVE SE SEE CONCEPT 2A SEE CONCEPT 1A G RECONSTRUCT DIVERTER. CONSIDERATIONS: 1. MAY REQUIRE RAISED BARRIER ALONG LANE TO PROVIDE ADDED PROTECTION. 2. PROVIDE STRAIGHT ALIGNMENT FOR BIKE 3. ACCOMMODATE PEDESTRIAN CONNECTIONS. BIKE BOULEVARD. LOW VOLUME AND HIGH RESIDENTIAL PARKING DEMAND. TWO-WAY PROTECTED BIKE LANE ON THE EAST SIDE TO CONNECT TO THE DIAGONAL TRAIL. A PROTECTED FACILITY MAY NOT BE FEASIBLE. TWO OPTIONS FOR CONSIDERATION INCLUDE: LEGEND OPTION D1: PROVIDE TWO-WAY PROTECTED BIKE LANES 1. REMOVE PARKING. THE CITY WILL NEED TO FURTHER INVESTIGATE FEASIBILITY OF PARKING STANDARD BIKE LANE OFF-STREET TRAIL REMOVAL. THIS MAY LIKELY NOT BE SUPPORTED. **BUFFERED BIKE LANE FUTURE OFF-STREET TRAIL** 2. FURTHER EVALUATION OF BIKE LANE TREATMENT MAY BE REQUIRED. PROTECTED BIKE LANE **EXISTING BIKE LANE** SPECIAL INTERSECTION TREATMENT **BIKE BOULEVARD** OPTION D2: PROVIDE SHARED LANE FACILITY 1. MAINTAIN PARKING MAY BE NEEDED SHARED BIKE LANE 2. STANDARD BIKE LANES DO NOT FIT WITHOUT PARKING REMOVAL. **DELINEATOR** REVIEW ALTERNATIVE ROUTE OR **BIKEWAY TYPE OPTIONS** PARKING REMOVAL PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY **FURTHER EVALUATION OF** TRAVEL LANE REMOVAL OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING. LONGER-TERM OPTIONS REQUIRED ADD PARKING PROTECTED BIKEWAYS FEASIBILITY ANALYSIS 233 Park Ave S, Ste 300 **FIGURE** MINNEAPOLIS Minneapolis, MN 55415

3:21:29 PM 3/4/2015 X:\2014\140091\DESIGN\PlanS NOTE:









233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 мам 612.758.3099 FAX www.alliant-inc.com OTECTED BIKEWAYS FEASIBILITY ANALYSIS


15TH ST SE TO NE DIAGONAL


PRELIMINARY CONCEPT

CORRIDOR 13


FIGURE A-13 1 OF 2

15TH ST SE TO NE DIAGONAL - CONCEPT DESIGN 13






(1A) 15TH AVE SE - UNIVERSITY AVE TO 6TH ST SE




(2A) 15TH AVE SE - 6TH ST SE TO ROLLINS AVE







(D1) 18TH AVE SE - COME AVE SE TO E HENNEPIN AVE




- (E) ROLLINS AVE 15TH AVE SE TO 17TH AVE SE





18TH AVE SE - COME AVE SE TO E HENNEPIN AVE -MAY REQUIRE A DESIGN EXCEPTION





- (G) ROLLINS AVE 17TH AVE SE TO 18TH AVE ST 18TH AVE SE - ROLLINS AVE SE TO COMO AVE SE



PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.







233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 MAIN ALLIANT 612.758.3099 FAX www.alliant-inc.com

OR

PROTECTED BIKEWAYS FEASIBILITY ANALYSIS 15TH ST SE TO NE DIAGONAL PRELIMINARY CONCEPT CORRIDOR 13


FIGURE A-13 2 OF 2






(A2) EMERSON AVE N - PLYMOUTH AVE N TO 33RD AVE N (LONG TERM CONSIDERATION WITH BRT) -DESIGN EXCEPTION REQUIRED

*2' GUTTER PAN / BITUMINOUS SEAMS




(B1) FREMONT AVE N - PLYMOUTH AVE N TO 33RD AVE N -PREXISTING APPROVED DESIGN EXCEPTION REQUIRED *2' GUTTER PAN / BITUMINOUS SEAMS

EMERSON AVE N - PLYMOUTH AVE N TO 33RD AVE N (LONG TERM CONSIDERATION WITH BRT) -DESIGN EXCEPTION REQUIRED



FREMONT AVE N - PLYMOUTH AVE N TO 33RD AVE N -PREXISTING APPROVED DESIGN EXCEPTION REQUIRED

CONNECTION TO EMERSON AVE BIKE BLVD AT 33RD AVE REQUIRES BICYCLIST TO BE ON THE RIGHT SIDE OF STREET TO ACCESS THE HALF CLOSER TO THE NORTH SIDE OF INTERSECTION.



NOTE:

PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.










233 Park Ave S, Ste 300 www.alliant-inc.com

PROTECTED BIKEWAYS FEASIBILITY ANALYSIS EMERSON/FREMONT AVE N PRELIMINARY CONCEPT

CORRIDOR 15

FIGURE A-15

PLYMOUTH & 8TH AVE NE - CONCEPT DESIGN 16



3:21:50 PM 3/4/2015








233 Park Ave S, Ste 300 Minneapolis, MN 55415 612.758.3080 MAIN 612.758.3099 FAX www.alliant-inc.com PROTECTED BIKEWAYS FEASIBILITY ANALYSIS
PLYMOUTH & 8TH ST NE
PRELIMINARY CONCEPT
CORRIDOR 16


FIGURE A-16




CORRIDOR 17

3:22:16 PM 3/4/2015


MAIN ST & MARSHALL AVE NE - CONCEPT DESIGN 17




(A) E HENNEPIN AVE TO 1ST AVE NE




(B) 1ST AVE NE TO 3RD AVE NE




(C) 3RD AVE NE TO 10TH AVE NE



(D) 10TH AVE NE TO 14TH AVE NE






(E2) 14TH AVE NE TO LOWRY AVE NE

NOTE:

PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.









3:22:40 PM 3/4/2015


3RD AVE/CENTRAL AVE - CONCEPT DESIGN 18



1C) WASHINGTON AVE TO 2ND ST S
-BIKE/BUFFER WIDTH LESS THAN 10'




(D) 1ST ST S TO 2ND ST NE -BIKE/BUFFER WIDTH LESS THAN 10'




*BITUMINOUS OVERLAYS THE GUTTER

2ND ST S TO 1ST ST S -BIKE/BUFFER WIDTH LESS THAN 10' -DESIGN EXCEPTION REQUIRED



(E) 2ND ST SE TO 5TH ST SE




(2C2) 2ND ST S TO 1ST ST S

NOTE:

PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.







PUBLIC WORKS

ALLIANT


www.alliant-inc.com

PRELIMINARY CONCEPT


CORRIDOR 19

1 OF 2


WASHINGTON AVE S - CONCEPT DESIGN 19








(C) I-35W BRIDGE TO 15TH AVE (PARKING REMOVAL SHOWN)





D 15TH AVE TO 19TH AVE

NOTE:

PRELIMINARY CONCEPT FOR PURPOSES OF DETERMINING THE FEASIBILITY OF PROTECTED BIKEWAY IMPLEMENTATION. WIDTHS ARE APPROXIMATE. CONCEPTS WILL BE FURTHER DEVELOPED DURING PRELIMINARY ENGINEERING.



